

Horse Barn Delivery Instructions

We require,

- Clearance height of approximately 15ft.
- Width clearance of 2ft wider than your barn(if the building is 12 ft wide we need 14' clearance)
- A driveway or path that meets all conditions above. If not we may not be able to deliver on schedule, depending on ground conditions.
- If gates are present they must be 12in+ wider than the width of the barn.
- If there are any steep hills, sharp turns, or creeks to cross, or narrow places please send us a short video clip of the route as you drive through with a vehicle or a UTV. Starting at the beginning of the road all the way to the site.
- Room to maneuver a truck/trailer
- A level site (optional pad made out of Packed clay or small gravel is preferred but not required).

-All changes must be approved before construction begins. Any changes made after construction has begun may result in an additional charge.

-Please take a moment before you order your barn. Can we get to the site? Which way do you want the barn facing? If it gets a lean too roof you may want to add that to the excavated site. Always make the pad 12" larger on all 4 sides to give room to set down properly.

-Although we will set the barn on any relatively level site, if not level site we aren't responsible for any issues such as twisting or if the barn looks out of square. We will make sure the doors latch properly but we don't level up barns with blocks. (this is so there are no gaps under the structure for a horse or other animal to get their feet out and break a leg)

- If you have any questions about delivery, please ask to speak with Dave or Josh to discuss delivery options, the best route to follow.

Call: 615-789-0062

Thank you for your cooperation!

~The Delivery Crew

